


# 実行予算書

集計日：2016/09/30

No	1			状 況	契約			
見 積 日	2015/7/1			担 当 者	昭和 一郎			
顧 客 名	甲府建設株式会社			設 計 者				
見 積 先	甲府 二郎 様			契 約 日				
工 事 名	サンプル設備工事			着 工 日				
工 事 場 所	甲府市丸の内3-28-9			竣 工 日				
見積有効期限	お見積後30日			予 算 提 出 日				
納 入 期 日				予 算 承 認 日				
御 支 払 条 件	工事請負契約書の通り							
備 考								
見 積 書 メ モ				実行予算メモ				
	見 積 金 額	実 行 金 額	注 文 金 額	予 算 残 高	実行粗利益	利益率	注文粗利益	利益率
工 事 計	700,000	610,000	123,000	487,000	90,000	13	577,000	82
法 定 福 利 費	23,738	20,686						
税 抜 金 額	723,738	630,686	123,000	507,686	93,052	13	600,738	83
消 費 税	57,899	50,455	9,840					
税 後 値 引								
税 込 金 額	781,637	681,141	132,840	548,301	100,496	13	648,797	83

No	項目	規格・摘要	実行数量	単位	注文数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	給水設備工事		1	式			87,000	87,000		昭和設備 株式会社	1-001	2015/07/10
	給湯設備工事		1	式			36,000	36,000		昭和設備 株式会社	1-001	2015/07/10
	排水設備工事		1	式			324,000		324,000			
	衛生器具設備工事		1	式			93,000		93,000			
	給水管引込工事		1	式			127,000		127,000			
	現場雑費		1	式			7,000		7,000			
	諸経費	上、下水道申請費を含む	1	式			66,000		66,000			
	値引き		1	式			-130,000		-130,000			
※	別途費用											
	水道利用加入金	136,500円										
	設計審査手数料・竣工検査手数料	8,700円										
	[値 引]											
	[工 事 計]						610,000	123,000	487,000			
	[法定福利費]						20,686					
	[合 計]						630,686	123,000	507,686			
	[消 費 税]						50,455	9,840				
	[税込み合計]						681,141	132,840	548,301			

No	項目	規格・摘要	実行数量	単位	注文数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	配管材料費									昭和設備 株式会社	1-001	2015/07/10
	耐衝撃性硬質塩ビ管	HIVP20	22	m	22		3,542	3,542		昭和設備 株式会社	1-001	2015/07/10
	耐衝撃性硬質塩ビ管	HIVP13	12	m	12		1,080	1,080		昭和設備 株式会社	1-001	2015/07/10
	架橋ポリエチレン管	13A 保温厚3mm	24	m	24		5,568	5,568		昭和設備 株式会社	1-001	2015/07/10
	配管用継手材料費		1	式	1		18,000	18,000		昭和設備 株式会社	1-001	2015/07/10
	管支持金物		1	式	1		1,810	1,810		昭和設備 株式会社	1-001	2015/07/10
										昭和設備 株式会社	1-001	2015/07/10
	屋内配管工事費									昭和設備 株式会社	1-001	2015/07/10
	耐衝撃性硬質塩ビ管(屋内)	HIVP 20	1	m	1		1,064	1,064		昭和設備 株式会社	1-001	2015/07/10
	架橋ポリエチレン管	13A	24	m	24		15,360	15,360		昭和設備 株式会社	1-001	2015/07/10
										昭和設備 株式会社	1-001	2015/07/10
	屋外配管工事費									昭和設備 株式会社	1-001	2015/07/10
	耐衝撃性硬質塩ビ管(屋外)	HIVP 20	21	m	21		13,440	13,440		昭和設備 株式会社	1-001	2015/07/10
	根切り埋戻し費		1	式	1		26,000	26,000		昭和設備 株式会社	1-001	2015/07/10
	消耗品雑材料費		1	式	1		1,136	1,136		昭和設備 株式会社	1-001	2015/07/10
	[小 計]						87,000	87,000		昭和設備 株式会社	1-001	2015/07/10

No	項目	規格・摘要	実行 数量	単位	注文 数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	配管材料費									昭和設備 株式会社	1-001	2015/07/10
	架橋ポリエチレン管	13A	19	m	19		12,160	12,160		昭和設備 株式会社	1-001	2015/07/10
	配管用継手材料費		1	式	1		9,500	9,500		昭和設備 株式会社	1-001	2015/07/10
	管支持金物		1	式	1		1,000	1,000		昭和設備 株式会社	1-001	2015/07/10
										昭和設備 株式会社	1-001	2015/07/10
	配管工事費									昭和設備 株式会社	1-001	2015/07/10
	架橋ポリエチレン管	13A	19	m	19		12,160	12,160		昭和設備 株式会社	1-001	2015/07/10
	消耗品雑材料費		1	式	1		1,180	1,180		昭和設備 株式会社	1-001	2015/07/10
	[小計]						36,000	36,000		昭和設備 株式会社	1-001	2015/07/10

No	項目	規格・摘要	実行 数量	単位	注文 数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	配管材料費											
	硬質塩ビ管	VU100	44	m			19,184		19,184			
	硬質塩ビ管	VU75	20	m			6,040		6,040			
	硬質塩ビ管	VU50	15	m			2,535		2,535			
	配管用継手材料費		1	式			22,000		22,000			
	管支持金物		1	式			7,000		7,000			
	小口径汚水柵	100-150	3	組			9,000		9,000			
	トラップ柵	300	2	組			5,600		5,600			
	雨水柵	300	4	組			9,200		9,200			
	屋内配管工事費											
	硬質塩ビ管(屋内)	VU75	2	m			6,384		6,384			
	硬質塩ビ管(屋内)	VU50	13	m			27,664		27,664			
	屋外配管工事費											
	硬質塩ビ管(屋外)	VU100	44	m			113,696		113,696			
	硬質塩ビ管(屋外)	VU75	18	m			35,568		35,568			
	硬質塩ビ管(屋外)	VU50	2	m			2,736		2,736			
	小口径汚水柵取付費	100-150	3	ヶ所			14,400		14,400			
	トラップ柵取付費	300	2	ヶ所			9,600		9,600			
	雨水柵取付費	300	4	ヶ所			19,200		19,200			
	消耗品雑材料費		1	式			14,193		14,193			
	[小計]						324,000		324,000			

衛生器具設備工事

集計日：2016/09/30

No	項目	規格・摘要	実行数量	単位	注文数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	ガーデンパン及び水栓柱	W=450, 900L	1	組			10,000		10,000			
	ガーデンパン及び水栓柱取付費		1	組			4,800		4,800			
	散水栓	散水栓BOX, T27NH13	1	組			2,925		2,925			
	散水栓取付費	散水栓BOX, T27NH13	1	組			4,000		4,000			
	洗濯機用水栓取付費		1	個			3,200		3,200			
	洗濯機パン取付費		1	個			8,000		8,000			
	洋風便器取付費		1	組			11,200		11,200			
	紙巻器取付費		1	個			2,000		2,000			
	洗面化粧台取付費		1	組			8,000		8,000			
	ユニットバス接続費		1	台			6,400		6,400			
	流し台接続費		1	組			4,000		4,000			
	エコキュート取付費		1	台			20,000		20,000			
	消耗品雑材料費		1	式			8,475		8,475			
	[小計]						93,000		93,000			

No	項目	規格・摘要	実行数量	単位	注文数量	単位	実行金額	注文金額	予算残高	発注先	注文No	注文日
	配管材料費											
	VP用ボール式ボール分水栓	75X20	1	個			8,492		8,492			
	伸縮可とう継手	20	4	個			14,400		14,400			
	逆止弁付ボール止水栓	20	1	個			7,833		7,833			
	メーターBOX	20	1	個			4,800		4,800			
	ブロック		2	個			200		200			
	SGP-VB	20	3	m			2,289		2,289			
	HIVP	20	2	m			312		312			
	配管工事費											
	分岐掘削工	75X20	1	ヶ所			29,500		29,500			
	分水栓取付工	75X20	1	ヶ所			2,490		2,490			
	管布設工（全面入替）	H=0.6 20	2	m			11,800		11,800			
	布設工	SGP-VB 20	3	m			8,640		8,640			
	ポリスリーブ取付工	75	1	ヶ所			390		390			
	止水栓取付工（BOX据付を含む）	20	1	ヶ所			1,500		1,500			
	擁壁穴明け費		2	ヶ所			4,800		4,800			
	保温工事費		1	式			4,000		4,000			
	埋設シート設置工		1	m			220		220			
	舗装切断工		4	m			1,440		1,440			
	舗装撤去工		1	式			3,200		3,200			
	舗装処理費		1	式			1,200		1,200			
	交通整理員		1	人工			12,000		12,000			
	消耗品雑材料費		1	式			3,194		3,194			
	占用届		1	件			4,300		4,300			
	[小計]						127,000		127,000			