

項目	規格・摘要	見積数量	合計数量	単位	(分類なし)	直接材料費	直接労務費	現場経費	現場人件費			
給水設備工事		1	1	式		34,070	66,930					
配管材料費												
耐衝撃性硬質塩ビ管	HIVP20	24	24	m		4,248						
耐衝撃性硬質塩ビ管	HIVP13	12	12	m		1,188						
架橋ポリエチレン管	13A 保温厚3mm	24	24	m		6,192						
配管用継手材料費		1	1	式		18,500						
管支持金物		1	1	式		1,872						
屋内配管工事費												
耐衝撃性硬質塩ビ管(屋内)	HIVP 20	1	1	m			1,330					
架橋ポリエチレン管	13A	24	24	m			19,200					
屋外配管工事費												
耐衝撃性硬質塩ビ管(屋外)	HIVP 20	23	23	m			18,400					
根切り埋戻し費		1	1	式			28,000					
消耗品雑材料費		1	1	式		2,070						
[小計]						34,070	66,930					
給湯設備工事		1	1	式		26,200	16,800					
配管材料費												
架橋ポリエチレン管	13A	19	19	m		15,200						
配管用継手材料費		1	1	式		9,800						
管支持金物		1	1	式		1,200						
配管工事費												
架橋ポリエチレン管	13A	19	19	m			15,200					
消耗品雑材料費		1	1	式			1,600					
[小計]						26,200	16,800					
排水設備工事		1	1	式		108,440	286,560					
配管材料費												
硬質塩ビ管	VU100	44	44	m		24,024						
硬質塩ビ管	VU75	20	20	m		7,280						
硬質塩ビ管	VU50	15	15	m		2,790						
配管用継手材料費		1	1	式		24,000						
管支持金物		1	1	式		7,500						

項目	規格・摘要	見積数量	合計数量	単位	(分類なし)	直接材料費	直接労務費	現場経費	現場人件費			
小口径汚水桝	100-150	3	3	組		10,740						
トラップ桝	300	2	2	組		6,360						
雨水桝	300	4	4	組		10,288						
屋内配管工事費												
硬質塩ビ管(屋内)	VU75	2	2	m			7,980					
硬質塩ビ管(屋内)	VU50	13	13	m			34,580					
屋外配管工事費												
硬質塩ビ管(屋外)	VU100	44	44	m			142,120					
硬質塩ビ管(屋外)	VU75	18	18	m			44,460					
硬質塩ビ管(屋外)	VU50	2	2	m			3,420					
小口径汚水桝取付費	100-150	3	3	ヶ所			18,000					
トラップ桝取付費	300	2	2	ヶ所			12,000					
雨水桝取付費	300	4	4	ヶ所			24,000					
消耗品雑材料費		1	1	式		15,458						
[小計]						108,440	286,560					
衛生器具設備工事		1	1	式		24,000	89,000					
ガーデンパン及び水栓柱	W=450, 900L	1	1	組		11,330						
ガーデンパン及び水栓柱取付費		1	1	組			6,000					
散水栓	散水栓BOX, T27NH13	1	1	組		3,580						
散水栓取付費	散水栓BOX, T27NH13	1	1	組			4,500					
洗濯機用水栓取付費		1	1	個			4,000					
洗濯機パン取付費		1	1	個			10,000					
洋風便器取付費		1	1	組			14,000					
紙巻器取付費		1	1	個			2,500					
洗面化粧台取付費		1	1	組			10,000					
ユニットバス接続費		1	1	台			8,000					
流し台接続費		1	1	組			5,000					
エコキュート取付費		1	1	台			25,000					
消耗品雑材料費		1	1	式		9,090						
[小計]						24,000	89,000					
給水管引込工事		1	1	式	4,300	47,560	74,140		14,000			
配管材料費												

項目	規格・摘要	見積数量	合計数量	単位	(分類なし)	直接材料費	直接労務費	現場経費	現場人件費			
VP用ボール式ボール分水栓	75X20	1	1	個		10,036						
伸縮可とう継手	20	4	4	個		16,320						
逆止弁付ボール止水栓	20	1	1	個		8,952						
メーターBOX	20	1	1	個		5,280						
ブロック		2	2	個		260						
SGP-VB	20	3	3	m		2,670						
HIVP	20	2	2	m		356						
配管工事費												
分岐掘削工	75X20	1	1	ヶ所			29,500					
分水栓取付工	75X20	1	1	ヶ所			2,490					
管布設工 (全面入替)	H=0.6 20	2	2	m			11,800					
布設工	SGP-VB 20	3	3	m			10,800					
ポリスリーブ取付工	75	1	1	ヶ所			390					
止水栓取付工 (BOX据付を含む)	20	1	1	ヶ所			1,500					
擁壁穴明け費		2	2	ヶ所			6,000					
保温工事費		1	1	式			4,500					
埋設シート設置工		1	1	m			220					
舗装切断工		4	4	m			1,440					
舗装撤去工		1	1	式			4,000					
舗装処理費		1	1	式			1,500					
交通整理員		1	1	人工					14,000			
消耗品雑材料費		1	1	式		3,686						
占用届		1	1	件	4,300							
[小計]					4,300	47,560	74,140		14,000			
現場雑費		1	1	式				8,000				
諸経費	上、下水道申請費を含む	1	1	式	80,000							
別途費用												
水道利用加入金	136,500円											
設計審査手数料・竣工検査手数料	8,700円											
[合計]					84,300	240,270	533,430	8,000	14,000			